NA_RDC Gen1_Site Guidance and Program Summary_v2

Global Building Design Risk & Resilience (GBDR)

Summary

This document provides site guidance and program summary for Regional Distribution Center (RDC) building internal conversions and Spec-to-Suit builds. The specifications outline minimum building design parameters for RDC operations launching in 2027 and beyond. For additional project criteria, see Appendices and Design Bulletins. Site specific teams shall assess existing site and building conditions and determine if existing site and building components may be reused to minimize alternation scope of work for cost efficiency. However, no compromise should be made on essential upgrades needed to meeting minimum operational standards, including but not limited to Yard RGM (Remote Gate Management) requirements and any other critical regulatory, safety, or operational criteria.

AWD Integration Status: This document includes preliminary, high-level guidance for the AWD sandbox within RDC Gen1 buildings. A dedicated ~19K sq. ft. sandbox area is proposed to support AWD inbound and outbound operations without impacting RDC storage cube. Final AWD requirements are pending leadership decision; a separate, detailed AWD guidance document will be issued upon finalization.




Figure 1: RDC 2026 - IIN2 Proxie (WWDE RDC Gen1 LTM7 05/01/2026, reference only, not to scale)




Figure 2: RDC 2027 - MFD of Gen1 RDC – (WWDE RDC Gen1 LTM7 05/01/2026, reference only, not to scale)

NA_RDC Gen1_Site Guidance and Program Summary_v2

Global Building Design Risk & Resilience (GBDR)

Capacity			
	RDC Gen1 Site Guidance v2 (1M sqft) BRS 09/14/2026 (with cross-belt) Link	**RDC Gen1 Site Guidance v2 (1.2M sqft)** BRS 09/11/2026 (with cross-belt) Link	*Notes* *(Orange color t ext highlights show updates from Gen1)*
Inbound Throughput (Weekly Units)	**5.7MM**	**7.4MM**	
New Vendor Freight / Transfer In	**74% / 26%**	**74% / 26%**	
Inbound Fluid / Pallet	**67% / 33%**	**67% / 33%**	
Cross-dock Volume	**40%**	**40%**	
Each Sort Technology	**UIS**	**UIS**	
Each Sort Percentage	**50% of OB volume**	**50% of OB volume**	
Storage Net Cube (ft3)	**5,480,000**	**7,000,000**	
Storage Bin Mix – Case / Pallet	**75% / 25%**	**75% / 25%**	
Outbound Throughput (Weekly Units)	**5.7MM**	**7.4MM**	
Max Outbound Arcs	**50**	**50**	
Peak Shift Headcount (PSHC)	**552**	**646**	*Includes AWD HC & Fixed HC (110), data received from WWDE on 9/18/2026*
Off-peak Shift Headcount	**470***	**550***	*85% of Peak Volume* ** Number is approximate, final number on site-by-site basis*
PIT Estimate	**199**	**245**	
PIT Fuel Type	**Hydrogen / Lithium**	**Hydrogen / Lithium**	*Use existing infrastructure (Only sites with existing H2 infrastructure to have H2)*

Site Specifications			
Site Acreage	**+/- 56 Acres**	**+/- 60.4 Acres**	

Associate Parking Stalls	497, 1:0.9 ratio to Peak Shift Headcount (PSHC) includes Fixed HC	582, 1:0.9 ratio to Peak Shift Headcount (PSHC) includes Fixed HC	*Based on Peak Shift Headcount at a ratio of 1:0.9. To be confirmed pending LT approval.*
Dock Doors (minimum)	80 30 dock doors for IB (includes 10 plumbed dock doors) 50 dock doors for OB (no plumbed dock doors)	90 35 dock doors for IB (9 Fluid Unload 3 Auger & Compactor 3 Non-Inventory 10 Pallet Unload 10 AWD Sandbox) 55 dock doors for OB (OB Pallet Loading with the alternate 3DD/4DD cadence)	NOTE: Detailed AWD requirements will be issued separately pending final leadership decision.
Dock Door Spacing (minimum)	13' on center (min)	13' on center (min)	*Line item added in v2 to highlight key attributes for site slection with existing building.*
Total Trailer Slips Range (Including dock door positions)	266	319	
# Guard House (Guard Shack)	(1) Primary Guardhouse for IB: 2x IB lanes, 10 queueing in total (1) Secondary Guardhouse for OB: 2x OB lanes, 5 queueing in total	(1) Primary Guardhouse for IB: 2x IB lanes, 10 queueing in total (1) Secondary Guardhouse for OB: 2x OB lanes, 5 queueing in total	*For BTS sites, two (2) guardhouses are required.* *For site-specific designs with existing yard constraints, provide IB/OB queueing requirements and confirm with TOM the number of lanes and guardhouses needed.*

Building Specifications			
Dock Door Configuration	Two Sides required: Cross Dock or L-Shape	Two Sides required: Cross Dock or L-Shape	
Total Building Area (ft2)	1M	1.2M	*Per WWDE, 1.2MM building is preferred to provide more storage cubes.*
Building Length (ft)	1,736’	1,848’	*FlexShell for reference*
Building Width (ft)	588’	640’	*FlexShell for reference*
Column Cadence (LxW) (ft)	L: 56’ preferred; W: 52’ preferred (existing cadence on site to remain)	L: 56’ preferred; W: 52’ preferred (existing cadence on site to remain)	*FlexShell for reference*
Minimum Clear Height (ft)	40'	40'	*Required for VNA Operations*
Maximum Ceiling Height (ft)	48'	48'	
Slab Thickness (in)	7" minimum	7" minimum	
Roof hung MHE (Roof Structural reinforcement)	Inbound/Outbound dock areas to be protected to accommodate ceiling hanging conveyance	Inbound/Outbound dock areas to be protected to accommodate ceiling hanging conveyance	*Per WWDE in Conditional Approval, roof-hung MHE and PID platforms are required to optimize operational efficiency, pending official leadership approval. Pre-con to confirm with WWDE for site-specific feasibility and cost impact.*
Mezzanine - PID Platform	A concrete mezzanine/platform for PIDs, size 190" X 75"	A concrete mezzanine/platform for PIDs, size 190" X 75"	
Rooftop Solar - Installed power	Per Site-specific Design	Per Site-specific Design	*Site-specific EoR and/or project execution team to define compliance with AHJ and other site-specific use cases.* *Refer to Appendix 23 – Associate Car Parking EV Charging Standards*

Fire Protection	**ESFR (Early Suppression Fast Response) pendent sprinklers - Reliable N28T3 (K-28) sprinklers required to meet fire protection requirements for the following scenario:** **•48’ max ceiling height, 40' clear floor height between speed bay** **•37’ (444") tall VNA racks. 70” racking aisles for VNA case (RDC design), 78” racking aisles for VNA pallet** **•3” Transverse flue space** **•Minimum 36” clearance between sprinkler deflector to top of storage**	**ESFR (Early Suppression Fast Response) pendent sprinklers - Reliable N28T3 (K-28) sprinklers required to meet fire protection requirements for the following scenario:** **•48’ max ceiling height, 40' clear floor height between speed bay** **•37’ (444") tall VNA racks. 70” racking aisles for VNA case (RDC design), 78” racking aisles for VNA pallet** **•3” Transverse flue space** **•Minimum 36” clearance between sprinkler deflector to top of storage**	*Refer to Appendix 18 – Amazon Fire Protection Standard* *Existing sites with ceiling heights exceeding 48’ is not preferred and may require additional fire protection, ceilings and/or racking aisle modifications.* ***NOTE: In situations when a selected site has less than 40' clear floor height and racking uprights are limited to 402", 48" wide Order Pickers and 60" aisles are feasible, and K-28 is not required. Site specific Architect and Fire Proection Engineer to confirm with WWDE and IDS for site specific composite layout. Larger building footprints (e.g., 1.2MM sqft vs 1MM sqft) result in increased roof spans that may require adjusted roof slope to maintain adequate drainage; however, the 48' maximum ceiling height and 40' clear floor height shall not be exceeded.***

Notes:
The temporary generator will provide power to the site until permanent utility service is established, with specific implementation details to be determined based on site conditions.
** When options exist within the program guidance and building requirements, the Preconstruction Manager and site design team should apply the most conservative (worst-case) scenario for every attribute.*

NA_RDC Gen1_Site Guidance and Program Summary_v2

Global Building Design Risk & Resilience (GBDR)

Electrical Utility Power Demand	Utility Power Demand - RDC Gen1 (1M sqft)				Utility Power Demand - RDC Gen1 (1.2M sqft)			
	Li-Ion PIT + Gas Heating		Li-Ion PIT + All-Electric		Li-Ion PIT + Gas Heating		Li-Ion PIT + All-Electric	
	kVA	Amps	kVA	Amps	kVA	Amps	kVA	Amps
	Demand Load	Demand Load	Demand Load	Demand Load	Demand Load	Demand Load	Demand Load	Demand Load
Site and building (excluding MHE, PIT and EV)	2,133	2,566	3,803 - 5,033	4,566 - 6,056	2,560	3,079	4,230 - 5,460	5,079 - 6,579
PIT charging	985	1,185	985	1,185	1,183	1,423	1,183	1,423
MHE	3,281	3,947	3,281	3,947	3,620	4,354	3,620	4,354
A. Site and Building	**6,399**	**7,698**	**8,069 - 9,299**	**9,688 - 11,188**	**7,363**	**8,856**	**9,033 - 10,263**	**10,856 - 12,356**
B. Truckyard EV (2 slips)	**120**	**160**	**120**	**160**	**120**	**160**	**120**	**160**
C. Associate Parking EV	**Per site-specific AHJ compliance requirements**		**Per site-specific AHJ compliance requirements**		**Per site-specific AHJ compliance requirements**		**Per site-specific AHJ compliance requirements**	
TOTAL Utility Power Demand (A+B+C)	**Sum of above three demands**		**Sum of above three demands**		**Sum of above three demands**		**Sum of above three demands**	
# Electrical Services Required (480VAC main switchboards)[1]	Up to 4 main switchboards to efficiently distribute power across the total building area. To be finalized by site EoR. When site power upgrade is required, EoR shall design a new switchboard that with camlock provisions outside of the building to connect temporary power generator, and have provisions for future tie-in with utility grid, maintaining operations flexibility at launch while awaiting utility upgrades				Up to 4 main switchboards to efficiently distribute power across the total building area. To be finalized by site EoR. When site power upgrade is required, EoR shall design a new switchboard that with camlock provisions outside of the building to connect temporary power generator, and have provisions for future tie-in with utility grid, maintaining operations flexibility at launch while awaiting utility upgrades			

Notes:

(1) ONLY applicable if the site gets secondary (480VAC) service from the utility. If the site gets a Primary Service (Medium Voltage), then the total utility power demand shall be used to coordinate with the utility company.

(2) Demand-Diversity factor applied: 50% for Li-Ion PIT; 40% for MHE based on legacy site consumption pattern.

(3) Electrical requirements and MDP capacity for the AWD Sandbox are under evaluation. The baseline RDC Gen1 electrical design does not account for AWD Sandbox loads; these shall be treated as additive scope. Site-specific design teams shall coordinate with WWDE and the EOR to reserve capacity once requirements are finalized.

NA_RDC Gen1_Site Guidance and Program Summary_v2

Global Building Design Risk & Resilience (GBDR)

Site			
	Item	Requirements	Reference
1	Site Selection and Site Specific Design	• Site selection due diligence must include a thorough surveying and an Open Space Capture (Video of the site to capture true site conditions and infrastructure) of the site and building to identify discrepancies between existing documentation and actual site conditions. Applicable to interior and exterior conditions. • Full site verification of existing conditions required prior to design finalization (i.e. overall layout, dock doors, electrical panels, etc)	
2	Traffic Interference Standards / Yard Curb Cuts	• Site access requires a minimum of 2 curb cuts, with 4 preferred. All designs must be reviewed with the local fire marshal, and deviations from standard curb cut count due to site constraints must be highlighted as a deviation during the design review.	**Appendix 7** Associate Parking Lot Design Standards V1.0
3	Associate Parking	• Assess the existing associate parking area, including layout, striping, bumps, signages and wheel stops. Retain current features if they meet standards. Update as necessary. • Evaluate options to achieve the minimum associate parking numbers based on the site specific PSHC if not provided by existing parking lots. • Site specific Civil Engineer shall evaluate the quantity and locations of associate parking curb cuts based on parking counts, traffic study, and existing conditions to ensure clear separation between truck and associate traffic. • Site teams to plan for additional security controls to mitigate risks if GSRA risk scores are High or Very High. • Parking area design to be reviewed and approved by WHS (including speed bumps, pedestrian corridors, fencing, bollards, etc.)	**Appendix 7** Amazon KoP Associate Lot Design Standards V1.0 **Appendix 12** Risk Assessment Driven Security (RADS) **Appendix 22** Amazon KOP NA Building Security Standard V2.0
4	Guard House	• Utilize the existing guard houses if Primary Guardhouse meets minimum specs of 9'-3" x 15'-11" (9' 4" x 24' 8" preferred) with glass Window facing exterior yard, at least one side exit/entrance door, and lenel secured. • Restroom at the guard house is to be provided for all sites unless associate restrooms are already present within 500 feet. A permanent restroom is the preferred solution. A modular restroom trailer is acceptable as an alternate for STS sites or conversions. Porta-Potty toilets are not permitted. • TDR/TOM warehouse access door is required close to guard house. • For Guard house drawings and details refer to TS09 and TS10 series. • RGM technology integration is required and planned for all new launch buildings. For BTS sites or sites with existing Primary and Secondary Guardhouses, refer to the NA RGM KOP Standard SGH2 Series for the OB Secondary Guard House with 2x OB lanes, and design 2x IB lanes for the Primary Guard House based on the RGM KOP Standard for TOM team approval, as there is no 2x lane IB in the current standard package. For sites where only one guard house is feasible, refer to the NA RGM KOP Standard SGH2.2 Series for infrastructure and equipment. • Provide impact bollard protection for inbound and outbound lanes from incoming traffic directions per Yard Design Standard.	**Appendix 8** Amazon KoP Yard Design Standard V2.0 **Appendix 10** Remote Gate Management (RGM) Design Standard V1.0 **Appendix 4** Amazon Standard Details V2.0

5	Trailer Yard	• **Assessment & Existing Conditions:** The site-specific Civil Engineer shall evaluate curb cut quantity and locations based on trailer parking counts, traffic study, and existing conditions to ensure clear separation between truck and associate traffic. Assess the existing trailer yard area, including layout, striping, signage, and wheel stops; retain current features if they meet current standards and are in good working order, otherwise update as necessary. Utilize existing trailer yard configuration, bringing striping up to current Amazon standards if it does not meet the standard parking trailer stall width noted below. • **Trailer Stall Specifications:** Standard dock door trailer stalls have minimum 13' centerline distance and 60' depth of 4000 PSI heavy-duty concrete, with striping aligned to the driver-side backing dock door cushion strip. Standard parking trailer stalls are 12' wide and 55' deep, with a 10' wide "dolly pad" of 4000 PSI heavy-duty concrete inset 10' from the front of the stall and a control joint every other stall (minimum) to mitigate paving damage from landing gear point loads. Include 'land-on-blue' requirements for all trailer parking stalls. • **Circulation & Maneuvering:** Driving aisles must maintain 70' clear minimum width between trailer stalls, 40' clear minimum for two-way traffic, or 20' minimum for one-way traffic where no adjacent trailer movements occur (pick-up, drop-off, drive aisles entering & exiting yard; roadway connecting yard area on opposite sides of the building, etc). Dead-end driving aisles must provide a 100' diameter turning circle or hammerhead turnaround designed to accommodate a WB-67 sleeper cab tractor with a 53' trailer. If existing yard is two-way flow and business line intends to convert to one-way flow, additional outbound guardhouse and RGM infrastructure is required (see #4 Guard House section above). If the trailer slip count is not met on the existing site, an offsite yard will be required for the building to be operational. • **Safety & Security Features:** Interior yard (back-to-back) stalls require wheel stops 8' from face of wheel stop to back of stall and an 8' clear inspection path between stalls for conducting trailer seal audits. Wheel stop placement is also required for perimeter trailer locations that do not have a 6" curb and 6' of unobstructed walk path (6' total width consisting of 5.5' from back of sidewalk to face of 6" curb, plus the 6" curb width). Provide 8' tall chain-link fence if existing fence is not provided; if existing fence is 6', upgrade to 8' tall or obtain a site-specific assessment with WWOS for exceptions. • **Dock Design Requirements:** Dock wells and sawtooth loading docks are to be avoided. Dock aprons must slope away from the dock wall at 1-2% with no cross-slope; if dock apron is noncompliant, site must include topping slab to meet operational criteria as base scope for tenant retrofit. • Include OptiPave as an alternate concrete paving system for trailer yards to reduce carbon emissions and support Amazon's Net Zero Carbon 2040 goal.	**Appendix 8** Amazon KoP Yard Design Standard V2.0 **Appendix 10** Remote Gate Management (RGM) Design Standard V1.0 **Appendix 4** Amazon Standard Details V2.0 **Appendix 5** NA Signage Guideline V5.0 **Appendix 3** Amazon Specifications (3PS) V2.1 - (Div32)
6	EV Charger and Infrastructure	• Physical Setup: Minimum 25ft cable length with management system, mounted on 4" high yellow pad (30" width), no wheel stops required • Only 2 EV trucker chargers required for RDC program, no seperate EV transformer or switchboard is needed. Utilizing warehouse's switchboard for EV charger power.	**Appendix 15** In-Yard Electrical Vehicle (EV) Charging Standards **Appendix 8** Amazon KoP Yard Design Standard V2.0
7	Site Lighting	• For yard lighting, existing lighting to be used for internal conversion sites, but spec-to-suit sites need to meet the latest amazon yard standards. • Refer to Flex Shell Design Criteria Division 26 5600 - Exterior Lighting. Where existing site lighting needs to be upgraded, modifications shall follow the design criteria. • Utilize existing poles and provide additional fixtures to meet foot-candle requirements. • Verify guard house lighting meets 10 fc requirements	**Appendix 8** Amazon KoP Yard Design Standard V2.0 - YS01-C03 & YS00-G01 **Appendix 7** Amazon KoP Associate Lot Design Standards V1.0 - AP01 series **Appendix 3** Amazon Specifications (3PS) V2.1 - (Div 26 5000) **Appendix 2** RDC Gen1 Template V1 - Design Criteria

8	Site Signage and Traffic Control	• Provide code compliant traffic signage. Provide striped crosswalks in associate parking lot, speed bumps, and stop signs. Modifications to existing curb cuts shall be avoided. • Include Standard Yard Signages for Spec-to-suit sites • All Yard signage needs to comply with the NA Signage standard: ◦ AS-19, 20, and 37 signage installation at all dock doors ◦ PG-28a graphics and signage installation at any dead-end turnaround ◦ AS-12 signage at inactive dock positions and building adjacent stalls, ◦ AS-55 (truck hoteling) in all climate zones ◦ AS-4, AS-5, AS-6, AS-7, AS-8, AS-9, AS-16, AS-19, AS-20, AS-26, AS-56 (climate zones 5+), PG-1, PG-5, PG,-10, PG-11, PG-12, PG-13, PG-14, PG-21, PG-22, PG-23, PG-24	**Appendix 5** NA Signage Guideline V5.0 **Appendix 4** Amazon Standard Details V2.0 **Appendix 8** Amazon KoP Yard Design Standard V2.0 - YS04 series **Appendix 3** Amazon Specifications (3PS) V2.1 - (Div 10 1400)
9	Smoking Shelter	• Provide (2) prefabricated smoking shelter. • Locate (1) 30’ from the associate main entrance and (1) near a remote breakroom. ◦ Smoker's area should be at a minimum 20 ft (or as required by local code) and at a maximum 500 ft (approximately 5-minute walk) from the office core entrance. ◦ Provide pedestrian access from shelter to associate entrance via sidewalk or dedicated pedestrian pathway. ◦ Provide bollards where vehicle traffic is located within 10' of smoker's shelter. ◦ Only fire-resistant ground cover permitted within 15 ft distance around smoker's area. ◦ Confirm the clearance from generator, transformer and other electrical equipments • For Remote Smoking Shelter - Refer to TS14-A01	**Appendix 4** Amazon Standard Details V2.0 **Appendix 7** Amazon KoP Associate Lot Design Standards V1.0 **Appendix 3** Amazon Specifications (3PS) V2.1 - (Div10)

Warehouse			
1	Floor Requirements - Site Selection / Due Diligence	• Floor flatness and levelness must meet VNA operational requirements, PIT requirements and Pedestrian (PED) requirements and shall be verified during site selection. • Funds to be allocated if corrections are needed.	**Appendix 3** Amazon Specifications (3PS) V2.1 - (Div 03 3650; 01 4540; 01 4542; 01 4565 & 01 4542) **Appendix 21** Amazon KOP NA Warehouse Storage Standard V1.0 - (WH00-02) **Appendix 19** Amazon KOP NA Structural Standard V1.0
2	Racking - VNA (case and pallet)	• VNA racking installations require specific attention to wire guidance systems anchored to concrete, including operational validation • Pivot line specifications and placement must be verified during installation phase • VNA specs should match the internal Amazon Global Static Racking Standards (not included in this Site Guidance Package). • **Min floor requirements:** VNA racking aisles require a defined traffic floor flatness meeting minimum Floor Flatness Index values, transverse Floor Flatness Index (Fmin) of 60 for rack heights up to 402 inches, and transverse Floor Flatness Index (Fmin) of 45 for rack heights up to 300 inches. Compliance must be verified through profileograph testing and, where the floor does not meet requirements, remediated by concrete grinding or full slab replacement as needed. • **Min aisle width:** Confirm with WWDE and IDS composite for site specific design. • **Min vertical clearance: Clearance above stored product -** Racking must be designed so the top of stored product maintains a minimum 3-foot (36-inch) vertical clearance from the deflector of the ceiling-level Early Suppression Fast Response (ESFR) fire sprinklers; the topmost load shall never exceed 36 inches below sprinkler heads. The top of the topmost load must remain no closer than 18 inches of any lower-hanging overhead devices (HVAC, lighting, building trusses); the designer is responsible for identifying all such interferences before final engineering. **Clearance above racking top floor structural** (per WHS Startup standards) - 7' overhead clearance from the top of the racking floor of the top bay to physical obstructions, and 9' overhead clearance if the physical obstruction is a fire sprinkler. **The most stringent clearance requirements, whether based on the racking structure or the stored product, shall be applied to ensure safety and regulatory compliance.** • Prior to installation, the racking installer shall survey the area and update drawings to confirm compliance.	**Appendix 3** Amazon Specifications (3PS) V2.1 - (Div 03 3570 & 01 4542) **Appendix 21** Amazon KOP NA Warehouse Storage Standard V1.0 - (WH02-01)

3	Dock Doors - Inbound	• Provide loading dock equipment package for required IB and OB dock doors including, clearly indicating dock door fan/light combo installations in GC scope. • Provide power drops for flex conveyors. Refer to site specific composite and for dock door positions • Inbound dock door areas include Ergoriders for fluid unload operations. The site-specific Structural Engineer of Record (SER) shall evaluate existing slab capacity at all inbound Ergorider operating locations and provide reinforcement recommendations to support Ergorider point loads. Slab remediation scope shall be confirmed during site-specific due diligence.	**Appendix 3** Amazon Specifications (3PS) V2.1 – (Div 11 1300; 083613 & 26 2050) **Appendix 4** Amazon Standard Details V2.0
4	Dock Doors - Outbound	• Provide loading dock equipment package for actively used dock doors. • Refer to site specific composite for dock door positions	**Appendix 3** Amazon Specifications (3PS) V2.1 – (Div 11 1300; 083613 & 26 2050) **Appendix 4** Amazon Standard Details V2.0
5	Auger and Compactor	• Auger and compactor to be provided based on WWDE MHE layout and Integrated Design System (IDS, previously Ops Design) composite, confirm site specific quantity with WWDE and IDS • All auger and compactor system that require to be relocated must include installation of exterior lockable disconnects to meet safety requirements on its new location.	**Appendix 3** Amazon Specifications (3PS) V2.1 – (Div 11 8226) **Appendix 6** Amazon KOP NA Building Safety Standard V2.0 - (Sheet AG-14) **Appendix 8** Amazon KoP Yard Design Standard V2.0 - (Sheet AG-14)
6	Powered Industrial Truck (PIT) Parking/Charging	• WWDE to provide Integrated Design System (IDS, previously Ops Design) with PIT Make, Model, and Dimensions to ensure parking space is wide enough to accommodate PIT. • Painted striping for PIT parking provided by the General Contractor. All bollards, wheel stops, and fueling/charging stations are provided by Amazon or others. • Coordinate parking and charging locations with site specific composite. • For sites utilizing Lithium-Ion PIT, refer to Flex Shell Design Criteria Division 26 2050 - Power Distribution, for electrical load criteria per charger. For sites utilizing hydrogen, refer to Appendix 12 & 17 • Utilize existing site Hydrogen Infrastructure if available. • If existing Hydrogen infrastructure is deemed that will to not be utilized, it must go through a formal decommissioning process with cost analysis and approval. • Powered Industrial Truck (PIT) aisle clearances must meet minimum width and height requirements per PIT type (Review Table at TS03-A01): One-Way High Mast PIT aisles require 8'-0" clear width / 12'-0" clear height; Two-Way High Mast PIT aisles require 14'-6" clear width / 12'-0" clear height; One-Way Low Mast Pit and Two-Way Low Mast PIT aisles require 8'-0" and 14'-6" clear width respectively / 9'-6" clear height • Pedestrian and pallet paths must be maintained and separated from PIT traffic: One-Way Pallet Aisles require 5'-0" width; Two-Way Pallet Aisles require 8'-0" width; Green Mile (pedestrian protected path, inside tape) minimum 36" clear width / 6'-8" clear height (in the US)	**Appendix 2** RDC Gen1 Template V1 - Criteria Division 26 2050 - Power Distribution **Appendix 1** RDC Gen1 Template V1 **Appendix 17** Hydrogen Area Requirements & Checklist **Appendix 4** Amazon Standard Details V2.0 - (TS15 series) **Appendix 8** Amazon KoP Yard Design Standard V2.0 - (YS08 series) **Appendix 3** Amazon Specifications (3PS) V2.1 - (Div 01 2000) **Appendix 6** Amazon KOP NA Building Safety Standard V2.0 - (SS03-A01)

7	Modules - Cages	• Provide chain-link cages, gates, and access controls. Refer to site specific composite for quantity and locations. Cages including but not limited to HR Safety Cage, IT Cage, PIT Maintenance Cage, RME Parts cage, RME Cut cage, RME storage cage, RME center, Regulated Waste Cage.	**Appendix 4** Amazon Standard Details V2.0 - (TS16 series) **Appendix 21** Amazon KOP NA Warehouse Storage Standard V1.0 - (WH03-01) **Appendix 3** Amazon Specifications (3PS) V2.1 - (Div 10 2200; 10 2600 & 10 2200) **Appendix 22** Amazon KOP NA Building Security Standard V2.0 - (SE2 & SE3 series)
8	Modules - Power and Data	• Coordinate power and data drops through the warehouse to modules, as located on the site-specific composite.	**Appendix 2** RDC Gen1 Template V1 - Design Criteria Division 26 2050 - Power Distribution **Appendix 3** Amazon Specifications (3PS) V2.1 - (Div 26 0500; Div 26 0533 & 27 5319)
9	**HRV (High Retail Value) Process / Modules**	• HRV is a new process being introduced to AFN (Amazon Fulfillment Network) starting with 2026 RDC sites. • Provide Physical security controls to secure HRV cages and HRV aisles. Controls for HRV cage include badged access with dedicated cameras. Controls for HRV aisles include badged access to PIT operators, light curtains, dedicated cameras and structurally reinforced aisle back plates.	**Appendix 22** Amazon KOP NA Building Security Standard V2.0 (SC06-T01; SC00-G03 & SC00-G03)
10	Electrical Room	• Utilize existing Electrical Rooms as available. • Specify larger electrical panels during initial design phase to accommodate revisions and future retrofits • Ensure power distribution analysis and drop locations are clearly defined in initial project layout	**Appendix 3** Amazon Specifications (3PS) V2.1 - (Div 26 2416 & Div 26 0500)

11	Emergency Backup Power	26 3213 - Generator System and Switching A. Provide a generator with multiple automatic transfer switches (one per service entrance) for life safety loads and an automatic transfer switch with Bypass Isolation for Tenant's standby loads. Provide standby power to all IDF cabinets and multiple standby transfer switches (one per service entrance). The generator shall be natural gas if available and acceptable by the local jurisdiction. The generator shall have weatherproof housing, a critical grade silencer, battery charger, and remote annunciators. B. Emergency generator power shall support the emergency lighting requirements throughout the facility, and Tenant's MDF, Demarc, and IDF cabinet power shall be connected to standby power. Provide two (2) remote annunciator panels for the generator. Locate one (1) at the main building entrance and one (1) within the Fire Pump room. C. Include a requirement to provide on-site training of operational requirements for the emergency generator with the appointed Facility Maintenance Manager. D. In jurisdictions that have adopted the 2017 NEC, provide a 400 amp 277/480V portable generator connection cabinet connected between the generator and its associated emergency power system main distribution panel. The portable generator connection cabinet shall be Trystar or equal. E. The following items are to be supported by the Generator: • **Emergency Lighting** • **Main Security Area/Employee Entry** • **All Life Safety Devices** • **IDF's** • **MDF Den / Flexmod** • **Primary Guardhouse** • **Demarc/Telecom System** F. If utilize existing S-DEN, MDF/S-DEN shall be provided with two (2) 400A utility and two (2) 400A generator feeds via two (2) ATS's. The second 400A is redundant and is a non-coincidental load. If installing new FlexMod, confirm with IT and Telecom for latest requirements. G. Locate the generator on the site a minimum of 50'-0" from all parking lot drains.	
12	Emergency Electrical Room	• Provide Inverter Rooms where emergency lighting inverters are provided for emergency lighting power.	**Appendix 1** RDC Gen1 Template V1
13	FlexMod	• Use FlexMod model # FLEX-5CAB-3MDF V2	**Appendix 3** Amazon Specifications (3PS) V2.1 - (Div 21 1317)
14	IDFs	• Provide power and data to IDF cabinets located throughout the warehouse per site-specific design. • IDF UPS Power Circuit: One (1) single-phase 208V, 30Amp dedicated circuit with L6-30R receptacle inside the IDF enclosure must be generator backed where generators are available; breaker requires lock to prevent accidental turn off and must not be in panels feeding material handling equipment. • Convenience Power: One (1) 120V duplex NEMA 5-20 receptacle inside enclosure for convenience power (not required to be dedicated circuit, must be independent of UPS circuits, and does not require generator backup). • Capacity Planning: Factor a total of 5kVA per cabinet for overall building capacity; all IDF circuits must remain powered on at all times, including throughout construction.	**Appendix 4** Amazon Standard Details V2.0 - (SD-E-701 series) **Appendix 3** Amazon Specifications (3PS) V2.1 - (Div 26 0500; Div 27 5319 & Div 26 0500) **Appendix 22** Amazon KOP NA Building Security Standard V2.0 - (SC03-SE01)
15	Demarc Room	• Utilize the existing Demarc Room if provided. Provide plywood walls covering the interior of the room.	
16	Fire Pump	• Utilize existing Fire Pump Room or Fire Pump House.	**Appendix 1** RDC Gen1 Template V1 **Appendix 4** Amazon Standard Details V2.0 - (TS11 series) **Appendix 18** Amazon KOP NA Fire Protection Standard Referenced

17	Roof Access	• Evaluate and modify existing roof access ladder/stair to ensure full OSHA compliance per 29 CFR 1910.23 standards, including proper angle, landing platforms, cage requirements, and fall protection measures as applicable.	**Appendix 6** Amazon KoP NA Building Safety Standard V2.0 **Appendix 4** Amazon Standard Details V2.0 - (TS12 series)
18	Davit Crane	• Provide a roof-mounted rotating Davit Crane (Basis of Design: OZ Lifting Products Tele-Pro OZTP1200DAV) at each roof access hatch location, mounted to the parapet wall or pedestal; capacity 1,200 lbs retracted / 550 lbs extended, 360° rotation, powder coat safety yellow finish • Crane shall be non-penetrating (rubber-coated base weights) unless required by the Authority Having Jurisdiction (AHJ); access stair and platform required if operating reel exceeds 48 inches above roof surface; independent load testing at 125% of maximum capacity required prior to acceptance • Owner personnel training on crane operation required at project closeout; 2-year manufacturer warranty required	**Appendix 3** Amazon Specifications (3PS) V2.1 (Div 11 1500) **Appendix 4** Amazon Standard Details V2.0 - (TS05-A02; SD-A-521 & SD-S-334)
19	Water Service Entry Room	• Utilize existing Water Service Entry Room	**Appendix 1** RDC Gen1 Template V1
20	Scrubber Dump	• Scrubbers dump to be provided. Provide hose bibs at scrubber dump.	**Appendix 2** RDC Gen1 Template V1 - Design Criteria Division 22 1031 - Scrubber Dump Areas **Appendix 4** Amazon Standard Details V2.0 - (TS15 Series) **Appendix 3** Amazon Specifications (3PS) V2.1 (Div 22 4000)
21	Watercoolers	• Provide plumbing and power for approximately 8-10 remote water coolers throughout the facility, with locations near the inbound and outbound docks, in addition to those in breakrooms. The total number of water dispensers will vary based on site size and headcount. All water coolers must be placed within 500 feet walking distance of workstations. • There shall be at least one dispenser in each breakroom and additional units positioned within one-minute walking distance of bathrooms. The number of dispensers is calculated based on the ratio of one dispenser per 400 associates. • Watercoolers to be provided by Startup. If an existing site has watercoolers that already meet the minimum criteria, no changes are to be made. • Specific sites may opt for bottle service if providing watercoolers disrupts timelines. • Startup to verify latest Internal Amazon Break Room Standards by GPO	**Appendix 2** RDC Gen1 Template V1 - Design Criteria Division 22 4070 - Water Coolers
22	Warehouse Lighting	• Assess the existing warehouse lighting system, including fixtures, whips, circuits, lenses, sensors, and mounting hardware; retain current features if they meet current standards and are in good working order, otherwise update as necessary. • Evaluate existing modular whips for age and condition, replacing them if older than 10 years or if proper length is required to accommodate fixture grid changes; coordinate whip specifications with the selected fixture manufacturer to ensure compatibility. • Existing lighting fixtures that have reached end of life must be replaced with new LED fixtures meeting current Amazon lighting standards, achieving a minimum L70 rated life of 80,000 hours (for fixtures >45W) or 60,000 hours (for fixtures <45W), with a 7-year warranty from date of beneficial occupancy. • The site-specific EOR shall review existing lighting circuit loads and capacities to determine if existing circuits can support new LED fixtures, replacing circuits only if capacity is insufficient for new fixture loads. • The EOR shall specify appropriate lenses, ALC (Automatic Light Control) sensors, and mounting hardware to match the operational needs of the warehouse space and coordinate with the racking layout. • Provide fixture manufacturer and model number documentation (including nameplate information and whip specifications) to Amazon for review and approval prior to procurement.	**Appendix 2** RDC Gen1 Template V1 - Design Criteria Division 26 5100 – Warehouse Lighting. **Appendix 3** Amazon Specifications (3PS) V2.1 - (Div 26 5000) **Appendix 21** Amazon KOP NA Warehouse Storage Standard V1.0

23	Remote Breakroom	• Utilize existing breakrooms if available. • Remote breakrooms shall meet 500’ maximum travel distance per Amazon Standards (not a building code requirement). • Standard design is to provide space for (16) seats per breakroom, casework with sink, power and data for microwaves and vending. However, due to RDC racking and PIT operations, site-specific design shall allocate sufficient breakroom capacity based on associate heat maps. Higher-density work areas such as IB/OB may require larger breakrooms, while very low foot traffic areas should reduce seating or remove the breakroom to optimize amenity utilization. PXT and GES Launch to evaluate based on site-specific composite layouts. • Confirm breakroom space requirements match current headcount. • Reference includes general remote breakroom requirements, please modify square footage based on building code and site-specific requirements.	
24	Remote Restroom	• Provide remote restrooms to meet 500’ maximum travel distance per building code requirement. • Locate remote restrooms near remote breakrooms provided. Utilize existing if provided. • Refer to TS18-A01.1	**Appendix 4** Amazon Standard Details V2.0 - (TS18 Series) **Appendix 3** Amazon Specifications (3PS) V2.1 - (Div 22 4000; 10 2800 & 22 4000)
25	Remote Janitor Room	• Provide (1) Janitor Room per remote Breakroom/restrooms Cluster • Provide (1) Janitor Room per Trucker's Lounge. If trucker's lounge is within 1min walking distance of other Janitor Room, this can be voided • For each Janitor's Room, Provide plumbing for mop sink and faucet, hot / cold water and drain connection for (1) commercial washer. • Refer to TS18-A01.1	**Appendix 4** Amazon Standard Details V2.0 - (TS18 Series) **Appendix 3** Amazon Specifications (3PS) V2.1 - (Div 22 4000)
26	Trucker Cage / Lounge	• Max. 500' walking distance to every Trucker's Cage/Lounge • Min. (1) Trucker Lounge per active dock wall, Trucker's Lounge to include (16) Seats and (1) restroom; OR (1) Trucker Lounge at corner location if positioned between two adjacent dock walls • Alternative Configuration (with TOM Team approval): (1) Trucker's Cage with integrated restroom per dock wall side (substitutes Trucker's Lounge requirement). It is the responsibility of the Site specific Architect to validate and optimize the quantity, location, and distribution of Trucker's Lounges and Trucker's Cages w/ Restroom to confirm compliance with the maximum 500' walking distance to restroom requirement, ensuring the minimum number of facilities necessary to meet operational needs for the specific site, dock wall configuration, and TOM Team requirements. • Provide chain-link cages, gates, and access controls for Trucker’s Cages. Provide chain-link ceiling. Provide a restroom accessed from within the cage for Truckers. • Refer to TS16-A01	**Appendix 4** Amazon Standard Details V2.0 - (TS16 Series) **Appendix 22** Amazon KOP NA Building Security Standard V2.0
27	Air Quality monitors	• Air Quality monitors required on exterior of building and interior for all sites in Arizona, California, Colorado, Idaho, Nevada, Oregon, Utah, and Washington. • GC to coordinate with Composite Drawings for Power Drops.	

28	HVAC	• For spec to suit and internal conversion buildings: • The HVAC system can utilize the existing system if modifications are needed. • For buildings that don't have existing HVAC systems or gas utilities, the site-specific design team should provide all-electric heat pumps as the baseline. Where sites have inadequate electric power, prioritize electric service needs for cooling. Refer to heat pump guidance to adequately size all-electric heat pump heating electrical service needs. Where the cost of obtaining and distributing gas service to RTUs is less than the cost of electrical upgrades to achieve an all-electric heat pump design, dual fuel heat pump (hp w/ supplemental gas) RTUs may be used. • All electric heat pump guidance: ◦ Cold climate heat pump, Inverter Driven Variable Speed Scroll Compressor technology, shall be specified based on heating capacity derations for site-specific ambient ASHRAE design temperatures. These heat pump RTUs technologies eliminate excessive supplemental heating requirements and therefore should be prioritized in such climates or where electrical service capacity is limited. ◦ Vapor injection compressor technology (AAON or approved equal) shall be specified for applications below 0°F at ASHRAE 99.6% winter design temperature or where electrical service capacity is limited. ◦ Site-specific engineering analysis is required by the Engineer of Record (EOR) to confirm applicability and verify that the selected technology meets project heating requirements. • Auxiliary/Emergency electric heater sizing: Verify electric heater (auxiliary) size and leaving heating air temperature with site-specific climate needs. Do not oversize electric heater if not required. Emergency electric heater is required to provide backup emergency heat during heat pump compressor lockout and shall be sized for a minimum of 80% of design heating load and to not exceed unit peak compressor amperage. Emergency heat will also be needed during historical winter ambient temperatures that are below the design (ASHRAE 99.6% winter design) to provide some heating but will not provide the standard indoor heating setpoints.	**Appendix 3** Amazon Specifications (3PS) V2.1 (Div 23 3439 & 23 0900)
29	HVLS Fans	• Provide High-Volume Low-Speed (HVLS) fans in high-occupancy associate areas with large open floor plates or elevated ceiling heights to sustain adequate air velocities at the occupied zones and mitigate thermal stratification. • Provide HVLS in dock door areas if duct work is not designed to provide heating down to the floor. • HVLS fan locations, quantity, size and mounting height must be coordinated with new composite layouts and power drops to avoid conflicts with other building systems (i.e. data / power / unistrut / camera systems). • The Engineer of Record (EOR) shall determine HVLS applicability and fan requirements based on space-specific occupancy conditions and fan mounting zone clear height requirements. • Refer to HVLS standard detail for additional placement requirements.	**Appendix 2** RDC Gen1 Template V1 - Design Criteria Division - (Div 23 3400) **Appendix 3** Amazon Specifications (3PS) V2.1 - (Div 23 3439)
30	EBMS	• Provide a local Building Management System (BMS), BacNet protocol, compatible with Tenant's Enterprise system provided through Niagara N4 platform for Office and Warehouse including heating only zones and heating/cooling zones. • Existing HVAC (RTUs + HVLS fans) that is resued shall be integrated to Tenant's Enterprise BMS (EBMS) platform. Units shall be evaluated for factory-mounted controller (FMC) compatibility with eBMS platform. Where existing unit controllers support BACnet MS/TP communication, they shall be integrated directly into the Niagara N4 BMS architecture via the Division 25 provided Network Area Controller (NAC) without controller replacement. Where existing controllers do not support an approved BACnet communication protocol, the unit manufacturer shall coordinate with GBD&E (Global Building Design & Engineering) for a vetting and approval process prior to any upgrade scope being finalized. Contractor to hire CBRE for master systems integration, which is found in tenant's Preferred Vendor spec 00 2000 of BMS.	**Appendix 3** Amazon Specifications (3PS) V2.1 ◦ Division 00 2000 ◦ Division 23 0900 ◦ Division 23 0993 ◦ Division 25 1300

AWD			
	Layout	• The AWD Sandbox requires approximately 19,000 sqft of dedicated floor space within the RDC Gen1 footprint, with a PSHC of (11) associates. The sandbox utilizes (9) dock doors and does not require dedicated trailer slips; trailer staging shall be coordinated with the existing AFN yard operations on a site-specific basis. Refer to the site-specific composite for dock door assignments and yard integration. • Electrical requirements and Main Distribution Panel (MDP) capacity for the AWD Sandbox are under evaluation and not yet defined at this stage. Site-specific design teams shall reserve capacity and coordinate with WWDE and the Electrical Engineer of Record (EOR) to accommodate future AWD electrical loads, including power drops for CBC, DSI, mechlite conveyors, and Cubiscan equipment, once requirements are finalized. • The AWD Sandbox includes an Ergorider that requires structural reinforcement of the slab in the designated operating area. The site-specific Structural Engineer of Record (SER) shall evaluate existing slab capacity and provide reinforcement recommendations to support Ergorider point loads. Slab remediation scope shall be confirmed during site-specific due diligence.	Final AWD requirements are pending leadership decision; a separate, detailed AWD guidance document will be issued upon finalization.

Hazmat

	Layout	• No Hazmat in RDC	

HRV (High Retail Value)			
	Layout	• RDC program includes HRV inventory, refer to #9 under the Warehouse requirements table above.	

Security Area			
	Security Installations	• All security installations must comply with Amazon CorpNet Global Design Guidelines, ensuring proper access control, surveillance, and intrusion detection systems per zone-specific requirements.	**Appendix 20** Amazon CorpNet Global Design Guidelines 2023_V3.0 **Appendix 22** Amazon KOP NA Building Security Standard V2.0 (SC00, SC01, SC03 & SC04 Series) **Appendix 4** Amazon Standard Details V2.0 - (TS00-SE01 & SD-SE-500 through SD-SE-533) **Appendix 12** Risk Assessment Driven Security (RADS)

Sustainability			
	Report	• Comply with construction sustainability reporting procedures	**Appendix 3** Amazon Specifications (3PS) V2.1 Division 01 3000

NA_RDC Gen1_Site Guidance and Program Summary_v2

Global Building Design Risk & Resilience (GBDR)

Inputs		1M	1.2M	
Item	Design Attributes			
1	PSHC	552	646	
2	Shift Breaks	Single Shift Break	Single Shift Break	
3	Flexshell Building Size	1M	1.2M	
4	# of Floors	1	1	
5	Dock Door Configuration	Cross-Dock	Cross-Dock	

Main Office & Wellfare Block			1M	1.2M		
Item	Room	Standard Ratio	# Required	# Required	Requirements	Appendix
1	General Requirements	-	-	-	• All Office & Welfare block requirements to match the latest requirements based on RDC site specific PSHC. • Window treatment and window covering to follow the 3PS Specifications	**Appendix 3** Amazon Specifications (3PS) V2.1 - (Div 12 2000)
2	Security Vestibule	• Number of Tandem Turnstiles = (PSHC ÷ 300) × 2, rounded up	2	4	• Utilize existing main entrance. Main office block shall be located at main entrance if none exists. • Coordinate security requirements with WWOS. • Refer to Flex Shell Design Criteria Division 11 1400 – Security Turnstile. Use	**Appendix 4** Amazon Standard Details V2.0 (TS17 Series) **Appendix 3** Amazon Specifications (3PS) V2.1 - (Div 11 1400; 08 5659; 08 4000 &23 3433) **Appendix 22** Amazon KOP NA Building Security Standard V2.0 - (SC00; SC01; SC02 & SC03 Series)
		• Number of By-Pass Doors equals number of Tandem Turnstiles	2	4		
3	Security	LP Screening Module Requirements: • 0-250 PSHC - Module #TBD • 250-700 PSHC - Module #30769 (2+1 Lanes): Min. 27'-8" • 701 - 1000 -PSHC - Module #1603 (4+1 Lanes): Min. 35'-6" • 1001-2000 PSHC - Module #2107 (5+1 Lanes): Min. 38'-9" • 2000+ PSHC - Module #2245 (5+2 Lanes): Min. 49'-5"	Module #30769 (2+1 Lanes): Min. 27'-8"	Module #30769 (2+1 Lanes): Min. 27'-8"	• Provide a Security Area at the associate main entry • (1) Security Desk with power & data - Refer to TS17-A02 for details • Provide a soffit to provide power and data to security screening machines adjacent to the security desk. • Provide exit screening modules that include primary and secondary screening areas as per required module.	
		Security Desk: • Module #22058	Module #22058 (10'-6" X 12'-5")	Module #22058 (10'-6" X 12'-5")		
4	Lockers	59% PSHC	330 Lockers (33 Stacks)	390 Lockers (39 Stacks)	• Day-use lockers • Provide a Locker Room between the Main Breakroom and Security Area. • Lockers are stacked ten tall within a footprint of 12” width x 18” depth.	
5	Restrooms facing Lockers	Quantity of Fixtures is Fixed: 6 (3 per gender)	6 Fixtures (3 per gender)	6 Fixtures (3 per gender)	• Provide restrooms adjacent to the Locker Room. These restrooms are for associate and visitor use prior to passing the security desk into the warehouse. • Quantity: 6 (3 per gender) - Refer to 2/TS18-A01.1	**Appendix 4** Amazon Standard Details V2.0 - (TS18 Series) **Appendix 3** Amazon Specifications (3PS) V2.1 - (Div 22 4000; 10 2800 & 22 4000)
6	Main Breakroom	# of Seats: • 50% PSHC for staggered shift breaks • 90% PSHC for single shift break (RDC is single shift break)	498 Seats (122) Tables of 4 + (5) Tables of 2	582 Seats (143) Tables of 4 + (5) Tables of 2	• Site-specific design AoR to validate whether the existing main break rooms can accommodate the new headcount. • The main breakroom is to be accessed from the main entry, prior to the security desk, via the locker room.	
		• # of Appliances:			• Provide (1-2) Breakroom Vending Areas, accessed from the Main	

7	Main Breakroom Vending Area	◦ Microwaves (1:25 PSHC) ◦ Beverage Machines (1:150 PSHC) ◦ Snack Machines (1:150 PSHC) ◦ Frozen Food Coolers (1:500 PSHC) ◦ Ice Machines (1:500 PSHC) ◦ Coffee Machines (1:500 PSHC) ◦ Lunch Storage Coolers (1:125 PSHC) ◦ Kiosks (1:500 PSHC)	23 4 4 2 2 2 5 2	26 5 5 2 2 2 6 2	Breakroom • Provide (1) Vending Storage room accessed from Breakroom Vending Area (approx. 150 sqf) • Site specific coordination is needed to determine the amount of vending equipment to be provided based on the total building power capacity and the headcount requirements.	
8	Lactation	• Size: ◦ Min (1) Lactation Space ◦ (3) Lactation Space (if total weekly HC > 1000) • Min. (1) Lactation Space per Floor • < 5-minute walk (+/- 1,000 ft) to nearest Lactation Space	Office Block: (3) Lactation Spaces ADA Accessible; (1+) Additional Remote Pod(s) to meet walking distance requirements.	Office Block: (1) Double Lactation Space ADA Accessible; (1+) Additional Remote Pod(s) to meet walking distance requirements.	• Requirements per DCI-1406: ◦ Min (1) Lactation space per building in the main office block, accessed from warehouse and Amazon Avenue. Refer to 1/TS18-A03. ◦ All workstations must be less than a 5-minute walk (average of less than 1000ft) to the nearest lactation space, including lactation pod modules. ◦ For buildings over 1,000 total weekly head count, provide minimum of (3) accessible dedicated lactation spaces, including lactation pod modules. ◦ For buildings with multiple floors, at least one (1) dedicated lactation space is required on each actively operating floor. (RDC is only one floor.)	**Appendix 4** Amazon Standard Details V2.0 - (TS18 Series)
9	Utility Room	N/A	1	1	• Provide (1) Utility Room. Defer to code requirements for Fire rating	
10	Large Restroom facing Warehouse	N/A	20 (10 per gender)	24 (12 per gender)	• Provide restrooms in the main office block, accessed from the warehouse and Amazon Avenue. • Refer to 2/TS18-A01 • Verify code minimum fixtures are provided throughout the facilities. • **Confirm with GES Launch and PXT for site-specific design water closet quantity.**	**Appendix 4** Amazon Standard Details V2.0 - (TS18 Series) **Appendix 3** Amazon Specifications (3PS) V2.1 - (Div 22 4000; 10 2800 & 22 4000)
11	Multifaith Room	• Size: ◦ Small if PSHC < 350 ◦ Medium if PSHC = 350-750 ◦ Large if PSHC >= 750+	Double	Double	• Provide (1) Double Multifaith Room at the main office block, accessed from the warehouse and Amazon Avenue. • Refer to TS18-A02 • Keep the existing multifaith room and ablution room as is if already available on site. An ablution room is required if to be deployed during	**Appendix 4** Amazon Standard Details V2.0 - (TS18 Series)
12	Wellness Center	Size: ◦ Small if PSHC < 399 ◦ Medium if PSHC = 400-999 ◦ Large if PSHC >= 1000+	Medium	Medium	• Provide (1) Wellness Center at the main office block accessed from the warehouse and Amazon Avenue. • No cameras within treatment areas. • Refer to TS18-A04	**Appendix 4** Amazon Standard Details V2.0 - (TS18 Series)
13	Training Room	N/A	1	1	• Provide training room for (118) seats with power and data for two instruction stations, ceiling mounted projector and projection screen recessed in ceiling. Provide operable partition for room to be divided into two separate	

14	IDF Room	N/A	1	1	• Provide (1) IDF Room for main office block	**Appendix 4** Amazon Standard Details V2.0 - (SD-E-701 series) **Appendix 3** Amazon Specifications (3PS) V2.1 - (Div 26 0500; Div 27 5319 & Div 26 0500) **Appendix 22** Amazon KOP NA Building Security Standard V1.1 - (SC03-SE01)
15	Open Office	N/A	See requirements on right	See requirements on right	• Provide space, power and data for (8) desks in the remaining open office area.	
16	Private Office	N/A	See requirements on right	See requirements on right	• Provide (6) enclosed offices: ◦ (1) General Manager ◦ (1) Lost Prevantion ◦ (1) HR Manager ◦ (1) Open office (2-3 Desks) ◦ (1)WHS Offices ◦ (1) Hotel Offices	
17	Conference Room	N/A	See requirements on right	See requirements on right	Provide (1) Conference Room with seating for (12) twelve.	
18	Janitor Room	• (1) Janitor room adjacent to every Restroom, Breakroom (remote included) and AMCare Room • Janitor's Rooms can be combined if are within 1min walking distance to the rooms that are serving as long as are not in different security zones	N/A	N/A	• Provide (1) Janitor Room adjacent to Breakroom & Lockers Restrooms • Provide (1) Janitor Room adjacent to Large Restrooms & Wellness Center room • For each Janitor's Room, provide plumbing for mop sink and faucet, hot / cold water and drain connection for (1) commercial washer. • Refer to TS18-A01.1	**Appendix 4** Amazon Standard Details V2.0 - (TS18 Series) **Appendix 3** Amazon Specifications (3PS) V2.1 - (Div 22 4000)
19	Recruiting Open Area	Fixed Size: 31'-6" x 88'-2"	See requirements on right	See requirements on right	• Keep the existing recruitment center on site. **Pre-con to align with WFS Launch if recruitment center is needed for the site.** If the site doesn't already have a recruitment center, Pre-con to align with WFS is needed to omit it from the building program or if necessary, provide the space as per design standard. • On site dedicated associate recruitment area needs to have access control. • Labor approvals will need to flow through the standard WFS Labor Due Diligence process to mirror standard Site Selection and CAR approvals.	**Appendix 1** RDC Gen1 Template V1

NA_RDC Gen1_Site Guidance and Program Summary_v2

Global Building Design Risk & Resilience (GBDR)

Appendix #	Appendix Name	Link
Appendix 1	RDC Gen1 Template V1	RDC Gen1 Template V1_(50% Set)
Appendix 2	RDC Gen1 Template V1 - Design Criteria	RDC Gen1 Template V1 - Design Criteria_(50% Set)
Appendix 3	Amazon Specification (3PS)	Amazon Specifications (3PS) v2.1.pdf
Appendix 4	Amazon Standard Details	GSD BD&E_Amazon Standard Details V2.0.pdf
Appendix 5	NA Signage Guideline	GSD BD&E NA Signage Guideline v5.0.pdf
Appendix 6	Amazon KoP NA Building Safety Standard	Amazon KOP NA Building Safety Standard V2.0.pdf
Appendix 7	Amazon KoP Associate Parking Lot Standard	Amazon KoP Associate Lot Design Standards V1.0.pdf
Appendix 8	Amazon KoP Yard Design Standard	Amazon KoP Yard Design Standards V2.0.pdf
Appendix 9	RDC Gen1 BRS	See Shield, internal use only
Appendix 10	Remote Gate Management (RGM)	Amazon KOP NA Remote Gate Management (RGM) Design Standard V1.0.pdf
Appendix 12	Risk Assessment Driven Security (RADS)	RADS-Basis_of_Design_C_E_Tel_Sec_v3.pdf
Appendix 15	In-yard Electrical Vehicle (EV) Charging Standards	Middle Mile In-yard EV Charging Template.pdf
Appendix 16	Special Safety Conditions	2024 Amazon Special Safety Conditions V3.pdf
Appendix 17	Hydrogen Area Requirements & Checklist	Customer Scope Requirements - Amazon TNS Sites Liquid - 2022 FEB.pdf
		TEMPLATE - Checklist - SITE Hydrogen Pad Review.xls
Appendix 18	Fire Protection Standard	Fire Protection Standard Rev11.pdf
Appendix 19	Structural Standard	Amazon KOP NA Structural Standard v2.0.pdf
Appendix 20	Amazon CorpNet Global Design Guidelines	Amazon CorpNet Global Design Guidelines 2023_V3.0.pdf
Appendix 21	Warehouse Storage Standard	Amazon KOP NA Warehouse Storage Standard v1.0.pdf
Appendix 22	Building Security Standard	Amazon KOP NA Building Security Standard V2.0.pdf
Appendix 23	Associate Car Parking EV Charging Standards	Associate Car Parking EV Charging Standards.pdf
		Associate Car Parking EV Charging Standards.pdf

Disclaimer:
For reference only. To be utilized for the scope outlined above. NO ADDITIONAL SCOPE from the reference docs should be included in projects.